
# LIGHTING STUDY EEAP PROGRAM FOR LETTERKENNY ARMY DEPOT



Approved to public released
Disciplance Unimited

U.S. ARMY ENGINEER DISTRICT, NORFOLK

CORPS OF ENGINEERS

NORFOLK, VIRGINIA

PERFORMED BY

19971021 302



THE QUALITY INSPECTED 8

ENTECH ENGINEERING, INC. READING, PENNSYLVANIA

VOLUME 1 OF 3

SEPT 1995

### DEPARTMENT OF THE ARMY

CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS
P.O. BOX 9005
CHAMPAIGN, ILLINOIS 61826-9005

REPLY TO ATTENTION OF:

TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited. Distribution A. Approved for public release.

Marie Wakeffeld,

Librarian Engineering

# **TABLE OF CONTENTS**

<b>SECTION</b>		<u>TITLE</u>	PAGE
VOLUME	1		
		duction	
1.0	EXE	CUTIVE SUMMARY 1-1 through	h 1-3
	1.1	Project Authorization and Objectives	1-1
	1.2	Synopsis of Findings	1-1
	1.3	Organization of Report	1-3
2.0	MET	THODOLOGY 2-1 through	n 2-25
	2.1	Government Requested Data	2-1
•	2.2	Site Information Collection Procedures	2-2
	2.3	Lighting Model	2-2
	2.4	Lighting Level Standards	2-9
	2.5	Electric Model	2-11

# TABLE OF CONTENTS - cont'd

<b>SECTION</b>		TITLE	<u>PAGE</u>
	2.6	Energy Value	. 2-14
	2.7	Energy Conservation Opportunities (ECOs)  2.7.1 Existing Condition Description  2.7.2 Proposed Condition Description  2.7.3 Implementation Cost Estimate  2.7.4 Energy Savings  2.7.5 Maintenance Savings  2.7.6 Discussion  2.7.7 Life Cycle Cost Analysis Summary  2.7.8 Spreadsheet Detailing 2.7.1 through 2.7.4	<ul> <li>2-15</li> <li>2-15</li> <li>2-15</li> <li>2-16</li> <li>2-16</li> <li>2-17</li> <li>2-17</li> </ul>
	2.8	Draft Report/Client Review/Final Report	. 2-25
3.0	FAC	ILITY DESCRIPTION 3-1 throu	1gh 3-5
•	3.1	General	. 3-1
	3.2	Survey Areas	. 3-1
	3.3	Operation Schedule	. 3-2
4.0	BILL	JING HISTORY	igh 4-14
	4.1	General	. 4-1
	4.2	Electricity	. 4-5 . 4-11

# TABLE OF CONTENTS - cont'd

<b>SECTION</b>	•	TITLE	<u>PAGE</u>
5.0	ENE	RGY CALCULATIONS 5-1 throu	gh 5-9
	5.1	General	. 5-1
	5.2	Lighting Model Summary	. 5-1
	5.3	Electric Model Summary	. 5-7
6.0	ENE	RGY CONSERVATION OPPORTUNITIES 6-1 throu	gh 6-8
	6.1	General	6-1
	6.2	Recommended ECOs	. 6-3
	6.3	Non-recommended ECOs	. 6-8
7.0	OPE	RATION AND MAINTENANCE PRACTICES	. 7-1
	7.1	Operation and Maintenance	. 7-1
8.0	CON	CLUSION 8-1 throu	gh 8-3
	8.1	Synopsis of Findings	. 8-1
	8.2	Future Energy Costs	. 8-1

## TABLE OF CONTENTS - cont'd

TITLE

**PAGE** 

	-	
<u>VOLUME</u>	2	
9.0	ATT	CACHMENTS
	9.1	A/E Contract
	9.2	Meeting Minutes and Monthly Reports
	9.3	Electric Bills and Rate Schedule
	9.4	Lighting Models
	9.5	Energy Conservation Opportunities

### **VOLUME 3**

**SECTION** 

10.0 LIGHTING SURVEY FIELD DATA

# 1.0 EXECUTIVE SUMMARY

### 1.1 Project Authorization and Objectives

This project was authorized under the general provisions of Executive Order 12902 with specific implementation under the Army's Energy Engineering Analysis Program (EEAP). Entech Engineering, Inc. was commissioned under Contract DACA01-94-D-0037, Delivery Order 0004 issued by USAED, Mobile and Administered by USAED, Norfolk (Mlecik). The objectives of the project are to research, identify, evaluate, and define energy saving projects that meet the Army's criteria and lead to energy savings at the Letterkenny Depot with respect to lighting. Details of the authorization and objectives of this report, which delineates our contractual arrangement with the government, may be found in Section 9.1.

### 1.2 Synopsis of Findings

Entech Engineering, Inc. surveyed over 2 million square feet of lighting in defined areas of seventy-two buildings along with the roadway and parking lot areas. Overall, we considered over 14,000 luminaires with an annual estimated operating cost of \$330,000. Entech prepared documentation for seventeen (17) Energy Saving Opportunities (ECOs) complete with cost estimates and life cycle cost analysis.

Eight (8) ECO projects are recommended with a total implementation cost of approximately \$1,000,000 and an energy savings of 7,300 mmBtu (2,100,000 kWh). The recommended ECOs are listed in Table 1.2.1.

**Letterkenny Army Depot** Recommended ECO's **Table 1.2.1** 

紊

mmBtu Payback (Yrs) 61.2 3.03 88.3 1.83 254.5 2.75	
	1 1 1 1
_	1
531.4 2.88	
4607 9.92	
1554 8.83	
56.9 7.19	
102.4 2.14	
	ı
	I
7,300	

23-May-95

# 1.3 Organization of Report

The report consist of three (3) volumes:

# Volume 1

Section 1	Executive Summary
Section 2	Methodology
Section 3	Facility Description
Section 4	Billing History
Section 5	Energy Calculations
Section 6	Energy Conservation Opportunities
Section 7	Operation and Maintenance Practices
Section 8	Conclusion

### Volume 2

Section 9 Attachments

### Volume 3

Section 10 Lighting Survey Field Data